

Project Verification Report

2021

COVER PAGE	
Project Verification Report Form (VR)	
BASIC INFORMATION	
Name of approved UCR Project Verifier / Reference No.	Enviance Services Private Limited
Type of Accreditation	☐ CDM or other GHG Accreditation ☒ ISO 14065 Accreditation
Approved UCR Scopes and GHG Sectoral scopes for Project Verification	01 Energy industries (Renewable/Non-Renewable Sources)
Validity of UCR approval of Verifier	30/09/2027
Completion date of this VR	09/01/2026
Title of the project activity	15.65 MW Bundled Wind Energy Project in India by Intech Group
Project reference no. (as provided by UCR Program)	UCR 539
Name of Entity requesting verification service (can be Project Owners themselves or any Entity having authorization of Project Owners, example aggregator.)	Vivid Emissions Reductions Universal Pvt. Ltd.
Contact details of the representative of the Entity, requesting verification service (Focal Point assigned for all communications)	Name: Lokesh Jain Email ID – lokesh.jain@viviidgreen.com
Country where project is located	India
Applied methodologies (approved methodologies by UCR Standard used)	ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources - Version 22.0
GHG Sectoral scopes linked to the applied methodologies	01 Energy industries (Renewable/Non-Renewable Sources)
Project Verification Criteria:	☒ UCR Standard ☒ Applicable

Mandatory requirements to be assessed	Approved Methodology ☒ Applicable Legal requirements /rules of host country ☒ Eligibility of the Project Type ☒ Start date of the Project activity ☒ Meet applicability conditions in the applied methodology ☒ Credible Baseline ☒ Do No Harm Test ☒ Emission Reduction calculations ☒ Monitoring Report ☒ No GHG Double Counting ☐ Others (please mention below)
Project Verification Criteria: Optional requirements to be assessed	☒ Environmental Safeguards Standard and do-no-harm criteria ☒ Social Safeguards Standard do-no-harm criteria
Project Verifier's Confirmation: The <i>UCR Project Verifier</i> has verified the UCR project activity and therefore confirms the following:	The UCR Project Verifier Enviance Services Private Limited, certifies the following with respect to the UCR Project Activity 15.65 MW Bundled Wind Energy Project in India by Intech Group ☒ The Project Owner has correctly described the Project Activity in the Project Concept Note version 1.2 (dated 30/08/2025) including the applicability of the approved methodology <i>ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources - Version 22.0</i> and meets

	the methodology applicability conditions and has achieved the estimated GHG emission reductions, complies with the monitoring methodology and has calculated emission reductions estimates correctly and conservatively. ☒ The Project Activity is likely to generate GHG emission reductions amounting to the estimated 27,026 tCO_{2e} annually, as indicated in the PCN, which are additional to the reductions that are likely to occur in absence of the Project Activity and complies with all applicable UCR rules, including ISO 14064-2 and ISO 14064-3. ☒ The Project Activity is not likely to cause any net-harm to the environment and/or society ☒ The Project Activity complies with all the applicable UCR rules¹ and therefore recommends UCR Program to register the Project activity with above mentioned labels.
Project Verification Report, reference number and date of approval	Verification Report UCR Reference number: 539 Date of approval: 19-02-2026

¹https://a23e347601d72166dcd6-16da518ed3035d35cf0439f1cdf449c9.ssl.cf2.rackcdn.com/Documents/UCRtermsandconditionsMay2025Ver11_230525172325112351.pdf

Name of the authorised personnel of UCR Project Verifier and his/her signature with date



Vidhya Muralikrishna
Quality Manager
Date: 19-02-2026

PROJECT VERIFICATION REPORT

Executive summary

The project activity is titled- “15.65 MW Bundled Wind Energy Project in India by Intech Group”. It is a wind-power Project which is spread across villages of Sakri in Maharashtra & villages in Bhelahadi Karnataka state in India. The project activity involves the wind bundle Sr. No 01 which is owned by Inno Automation. (Project Proponent or PP) having the total installed capacity of 2.5 MW and consists of 2 Wind turbine generators (WTGs) each of 1.25 MW capacity in Dhule district of Maharashtra. The wind bundle Sr. No 02 is owned by Intech Automation – (Project Proponent or PP) The total installed capacity is 2.5 MW wind power project in dhule of Maharashtra. PP consists of 2 WTGs of 1.25 MW each. The wind bundle Sr. No 03 Intech Power Kovai is the total installed capacity is 1.25 MW and consists of one WTG in Dhule district of Maharashtra.

The wind farm bundle Sr. No 04 is owned by Intech Power Chennai pvt ltd – (Project Proponent or PP) having 2 states in that Maharashtra & Karnataka in which the total capacity is 9.4 MW. Maharashtra having 6.25 MW & Karnataka 3.15 MW.

The bundled wind power projects, owned by Inno Automation, Intech Automation, Intech Power Kovai, and Intech Power Chennai Pvt Ltd, aim to generate clean electricity through renewable wind energy. Project activity consists of 24 WEGs (1.25) kw (MH) & 0.225 kw (KA) of Suzlon make S-66. The project is owned by Inno Automation, Intech Automation, Intech Power Kovai, and Intech Power Chennai Pvt Ltd.

The project involves the supply, erection, commissioning, and operation of these machines, managed by Suzlon, which serves as the equipment supplier and Operation and Maintenance contractor.

The wind farm generates approximately **79,236.97 MWh** of clean electricity in the current monitoring period. The generated electricity is supplied to the state electricity utility MSEDCL & KPTCL under a long-term power purchase agreement (PPA). which is part of the INDIAN (Northern, Eastern, Western and North Eastern) grid (now merged in the integrated Indian grid) in India, under a long-term power purchase agreement (PPA) and business transfer agreements signed between the following:

On September 1, 2020, Inno Automation India Pvt Ltd entered into Business Transfer Agreements (BTAs) with two sellers: Palms Enercon Inc (Seller Location: G006) and Chawala Brothers Pvt Ltd (Seller Location: K295) for the acquisition of their respective business assets. Substation for Maharashtra turbine Jamde/220kv

Additionally, on August 1, 2020, Intech Automation Private Limited signed a BTA with Kajaria Ceramics Limited (Seller Locations: K103 and K104) for a 2.50 MW project.

Furthermore, a Power Purchase Agreement (PPA) was executed between Maharashtra Electricity Distribution Company Limited for a 6.25 MW capacity, covering projects at multiple

locations: Project Location K132, J 095, J 096, J 097, J 098 Tal. Sakri, Dist. Dhule, Maharashtra.

A Business Transfer Agreement (BTA) for Turbine No. G1 and G31 was signed between M/s BSC Textiles and M/s Intech Chennai Pvt. Ltd. on June 7, 2019. Substation for Karnataka site Gadag 110/33kv

Turbines No. G3, G4, G7, G8, G11, G12, G32, G33, and G34 are associated with M/s B.S. Channabasappa & Sons and M/s Intech Chennai Pvt. Ltd. June 7, 2019.

Turbine No. G19 is associated with M/s SK Shashidhar and M/s Intech Chennai Systems Pvt. Ltd. June 7, 2019.

Turbine No. G10 is associated with M/s Shree Channeshwara Drier and M/s Intech Chennai Systems Pvt. Ltd. June 7, 2019.

The expected operational lifetime of the project is for 20 years. Addressing the energy demand-supply gap in Maharashtra and Karnataka and supporting the region's sustainable growth.

The first WEC under the project activity was commissioned on 30/06/2005 and the last WEC under the project activity was commissioned on 13/08/2008. The project has been operational since the earliest commissioning date.

The project activity has not been registered or applied for voluntary carbon benefits under any other GHG program. PP seeks verification under UCR from 01/09/2020 onwards, i.e., crediting period for UCR starts from 01/09/2020 to 31/12/2024. Hence, there is no double counting for the said project.

The project activity consists of 24 WEGs (1.25) kw (MH) & 0.225 kw (KA) of Suzlon make S-66 type Wind Energy Converters (WECs).

Commissioning dates of the project activity are mentioned in the table below:

Customer Name	Substation	No Of WEC	Capacity	HTSC No.	Commissioning Dates
Inno Automation India Pvt Ltd	Jamde/220kv	1	1.25	K295	21.03.2006
Inno Automation India Pvt Ltd	Jamde/220kv	1	1.25	G06	31.12.2005
Intech Automation Pvt Ltd	Jamde/220kv	1	1.25	K103	29.09.2005
Intech Automation Pvt Ltd	Jamde/220kv	1	1.25	K104	30.09.2005
Intech Power Kovai Pvt Ltd	Jamde/220kv	1	1.25	K294	21.03.2006
Intech Systems Chennai Pvt Ltd	Jamde/220kv	1	1.25	K132	30.06.2005

Project Verification Report

Intech Systems Chennai Pvt Ltd	Jamde/220kv	1	1.25	J095	29.09.2006
Intech Systems Chennai Pvt Ltd	Jamde/220kv	1	1.25	J096	29.09.2006
Intech Systems Chennai Pvt Ltd	Jamde/220kv	1	1.25	J097	29.09.2006
Intech Systems Chennai Pvt Ltd	Jamde/220kv	1	1.25	J098	29.09.2006
Intech Systems Chennai Pvt Ltd	Gadag 110/33kv	1	0.225	IGT 01	21.02.2008
Intech Systems Chennai Pvt Ltd	Gadag 110/33kv	1	0.225	IGT 02	21.02.2008
Intech Systems Chennai Pvt Ltd	Gadag 110/33kv	3	0.675	IGT 03, 04 & 08	21.02.2008
Intech Systems Chennai Pvt Ltd	Gadag 110/33kv	1	0.225	IGT 05	21.02.2008
Intech Systems Chennai Pvt Ltd	Gadag 110/33kv	1	0.225	IGT 07	21.02.2008.
Intech Systems Chennai Pvt Ltd	Gadag 110/33kv	1	0.225	IGT 10	21.02.2008
Intech Systems Chennai Pvt Ltd	Gadag 110/33kv	1	0.225	IGT 11	21.02.2008
Intech Systems Chennai Pvt Ltd	Gadag 110/33kv	1	0.225	IGT 12	21.02.2008
Intech Systems Chennai Pvt Ltd	Gadag 110/33kv	1	0.225	IGT 31	13.08.2008
Intech Systems Chennai Pvt Ltd	Gadag 110/33kv	2	0.45	IGT 32 & 34	21.02.2008
Intech Systems Chennai Pvt Ltd	Gadag 110/33kv	1	0.225	IGT 33	21.02.2008

Geo Co-ordinates of the project activity are mentioned in the table below:

Customer Name	Capacity	Site	Capacity		Geo Coordinates
			HTSC No.	Total Mw	
Inno Automation India Pvt Ltd	1.25	Sakri	K295	15.65	21°11'37.6"N, 74°12'30.7"E
Inno Automation India Pvt Ltd	1.25	Sangli	G06		17°10'04.6"N, 74°54'50.3"E
Intech Automation Pvt Ltd	1.25	Sakri	K103		21°13'04.6"N, 74°19'35.1"E
Intech Automation Pvt Ltd	1.25	Sakri	K104		21°13'12.1"N, 74°19'52.9"E
Intech Power Kovai Pvt Ltd	1.25	Sakri	K294		21°11'55.5"N, 74°12'48.1"E
Intech Systems Chennai Pvt Ltd	1.25	Sakri	K132		21°13'57.9"N, 74°24'02.0"E
Intech Systems Chennai Pvt Ltd	1.25	Sakri	J095		21°14'14.5"N, 74°24'02.2"E

Intech Systems Chennai Pvt Ltd	1.25	Sakri	J096		21°14'01.8"N, 74°24'21.0"E
Intech Systems Chennai Pvt Ltd	1.25	Sakri	J097		21°14'25.4"N, 74°24'33.3"E
Intech Systems Chennai Pvt Ltd	1.25	Sakri	J098		21°11'54.5"N, 74°17'53.4"E
Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 01		15°20'10.3"N, 75°36'58.7"E
Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 02		15°20'12.3"N, 75°36'52.4"E
Intech Systems Chennai Pvt Ltd	0.675	Gadag	IGT 03, 04 & 08		15°20'06.8"N, 75°36'52.8"E
Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 05		15°20'09.6"N, 75°36'45.9"E
Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 07		15°20'15.9"N, 75°36'45.8"E
Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 10		15°20'12.5"N, 75°36'38.1"E
Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 11		15°20'07.3"N, 75°36'38.6"E
Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 12		15°20'04.6"N, 75°36'31.1"E
Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 31		15°20'15.4"N, 75°36'23.5"E
Intech Systems Chennai Pvt Ltd	0.45	Gadag	IGT 32 & 34		15°20'12.4"N, 75°36'17.5"E
Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 33		15°19'46.2"N, 75°36'19.0"E

Proposed wind power project has evolved as a result of the policies of Government of India and Government of Maharashtra and Karnataka, which encourages energy development from renewable sources. These policies have given fresh impetus to wind power generation.

The Project Activity is a greenfield wind project and the generated electricity is supplied to the state electricity utility MSEDCL & KPTCL. Addressing the energy demand-supply gap in Maharashtra and Karnataka and supporting the region's sustainable growth. A Power Purchase Agreement and a Business Transfer Agreement has been signed various entities and different owners. The project activity consists of 24 WEGs (1.25) kw (MH) & 0.225 kw (KA) of Suzlon make S-66 type Wind Energy Converters (WECs) with internal electrical lines connecting the project activity with local evacuation facility, set up by Suzlon in India. These wind turbines convert wind energy into electricity using synchronous generators, which are manufactured at Suzlon and are spread across villages of Sakri in Maharashtra & villages in Bhelahadi Karnataka state in India. The generated electricity is evacuated at Jamde/220kv substation in Maharashtra and Gadag 110/33kv substation in Karnataka. The internal electrical lines connect the Project with local evacuation facility. The WECs generates 3-phase power at 400V, which is stepped up to 33 KV. The Project can operate in the frequency range of 47.5–51.5 Hz and in the voltage range of 400 V $\pm$ 12.5%.

Plant using advanced vacuum impregnation technology for better insulation and durability. The turbines have rotor blades, a nacelle with the generator and control systems, a tower, and a concrete foundation. The electricity generated is fed into the Indian grid through transformers. Without this project, the same amount of electricity would come from fossil fuel-based power plants, which is the baseline scenario. This renewable energy project reduces emissions and supports local manufacturing through technology transfer.

The average lifetime of the WEG is around 20 years as per the industry standards. As per DPR plant load factor is of 20%. The project being a renewable energy generation activity, leads to reduction in fossil fuel dominated electricity generation from the Indian grid.

The core objective of this project activity is to displace an equivalent amount of electricity which would have otherwise been generated by fossil fuel dominant electricity grid. The estimated lifetime of the project activity is considered as 20 years for wind technology. In the Pre- project scenario the entire electricity, consumed by the customers or delivered to the grid by, would have otherwise been generated by the operation of grid-connected power plants and by the addition of new generation sources.

The project activity consists 24 WEGs (1.25) kw (MH) & 0.225 kw (KA) of Suzlon make S-66 type. This project generates 15.65 MW power which is supplied to the state electricity utility delivered by the Project Proponent. The applied technology is one of the most environment friendly technologies available as the operation of the wind power plant does not emit any GHGs or any other harmful gases unlike the operation of conventional power plant. The project activity has used the reliable and proven technology to ensure that an environmentally safe and sound technology has been implemented.

The main component of this project activity is wind turbine which consists of components like main tower, blades, nacelle, hub, main shaft, gear box, bearing and housing, brake and generator. The generation of power from wind turbines is a clean technology as there is no fossil fuel-fired or no GHG gases are emitted during the process. Thus, project activity leads to a reduction the GHG emissions as it displaces power from fossil fuel-based electricity generation in the regional grid. Since the project activity generates electricity through wind energy, it will not cause any negative impact on the environment and thereby contributes to climate change mitigation efforts.

The project activity also contributes to SDG goals 7,8 and 13.

The first crediting period of the project activity in UCR is 04 years, 04 months in which total estimated electricity generation is 31,532 MWh annually and the total GHG emission reduction estimated is 27,026 tCO₂e annually.

The electricity generation for the current monitoring period is 79,236.97 MWh and total GHG emission reduction is 69,161 tCO₂e.

Scope of Verification

The scope of the services for the project is to perform Project Verification of concerned Project Activity. The scope of verification is to assess the claims and assumptions made in the Project Concept Note (PCN) and Monitoring Report (MR) against the UCR criteria, including but not limited to, UCR program verification guidance document, UCR Standard, UCR Program Manual, and related rules and guidelines established under Program process.

Verification Process and Methodology

The verification process was undertaken by a competent verification team and involved the following,

- Desk review of documents and evidence submitted in context of the reference rules and guidelines issued by UCR,
- Undertaking/conducting site visit/remote audit, interview or interactions with the representative of the project owners/representatives,
- Reporting audit findings with respect to clarifications and non-conformities and the closure of the findings, as appropriate and preparing a draft verification opinion based on the auditing findings and conclusions
- Finalization of the verification opinion (this report)

Desk/Document review

A detailed desk review of the PCN, MR, Methodology and all other associated documentation and references took place in advance of the site visit, and additional documents that were not available for the desk review were requested for review during the site visit. Additional information can be required to complete the verification, which may be obtained from other public and reliable sources or through telephone and face to face interviews with key stakeholders (including the project developers and where necessary, government and NGO representatives in the host country).

A list of all documents reviewed or referred to in the course of this verification is included in Appendix 3 below.

Follow up interviews/site visit

The verifier conducted remote audit and had requested for site photographs, short videos. A remote interview was conducted with the project owners and stakeholders.

Conclusion

Based on the work performed, the verifier concludes that in the project activity “15.65 MW Bundled Wind Energy Project in India by Intech Group”, the information and data presented in the MR version 1.1 dated 08/01/2026 is in line with the Project Concept Note Version 1.2 date 30/08/2025 and meets all relevant requirements of the UCR for UCR project activities. The UCR project activity correctly applies the methodology “ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version

22.0” leading to result in real, measurable and long-term emission reductions achieved for the current monitoring period.

For the current monitoring period, verified emission reductions achieved by the project activity were as below;

Start date of monitoring period	01/09/2020
End date of monitoring period	31/12/2024
Emission reductions achieved	69,161 tCO ₂ eq

Project Verification team, technical reviewer and approver

Project Verification team

No.	Role	Last name	First name	Affiliation (e.g. name of central or other office of UCR Project Verifier or outsourced entity)	Involvement in		
					Doc review	Off-Site inspection	Interviews
1.	Team Leader/ Lead Verifier	Mahajan	Swati	Enviance Services Private Limited	Yes	Yes	Yes
2.	Validator- Verifier/Technical Expert	Singh	Ritu	Enviance Services Private Limited	Yes	Yes	Yes

Technical reviewer and approver of the Project Verification report

No.	Role	Type of resource	Last name	First name	Affiliation (e.g. name of central or other office of UCR Project Verifier or outsourced entity)
1.	Technical reviewer	Internal	Kumar	Pankaj	Enviance Services Private Limited
2.	Approver	Internal	Krishna	Vidhya Murali	Enviance Services Private Limited

Means of Project Verification

Desk/document review

A detailed desk review of the PCN, MR, methodology and all other associated documentation and references took place in advance of the remote audit, and additional documents that were not available for the desk review were requested for review during the remote audit. Additional information can be required to complete the verification, which may be obtained from other public and reliable sources or through telephone and face-to face interviews with key stakeholders (including the project developers and where necessary, Government and NGO representatives in the host country).

A list of all documents reviewed or referred to in the course of this verification is included in Appendix 3 below.

Off-site inspection

Date of off-site inspection: 31/07/2025			
No.	Activity performed Off-Site	Site location	Date
1.	a) An assessment of the implementation and operation of the project activity as per the PCN and UCR requirements b) Verification of the project design, as documented is sound and reasonable, and meets the identified criteria of UCR Standard Requirements and associated guidance c) Assessment to conformance with the certification criteria as laid out in the UCR Standards; d) Evaluation of the conformance with the certification scope, including the GHG project and baseline scenarios, additionality; GHG sources, sinks, and reservoirs; and the physical infrastructure, activities, technologies and processes of the GHG project to the requirements of the UCR; e) Evaluation of the calculation of GHG emissions, including the correctness and transparency of formulae and factors used; assumptions related to estimating GHG emission reductions; and uncertainties; and determination whether the project could reasonably be expected to achieve the estimated GHG reduction/removals. f) Review of information flows for generating, aggregating and reporting of the parameters to be monitored g) To confirm that the operational and data collection procedures can be implemented in	Villages of Sakri in Maharashtra & villages in Bhelahadi Karnataka state in India.	31/07/2025

	accordance with the Monitoring Plan h) Cross-check of information provided in the submitted documents and data from other sources available at site i) Review of calculations and assumptions made in determining the GHG data and estimated ERs, and an identification of QA/QC procedures in place to prevent, or identify and correct, any errors or omissions in the reported monitoring parameters Interviews of local Stakeholders		
--	--	--	--

Interviews

No.	Interview			Date	Subject
	Last name	First name	Affiliation		
1.	Chandran	Pratap	Intech Power	31/07/2025	Project Implementation, Monitoring plan, Project Boundary, Eligibility criteria, Host country requirements, Emission reduction calculations Project implementation, monitoring, Local stakeholder consultation
2.	B.	Thippeswamy			
3.	-	Regupathy			
4.	Pathak	Nidhi	Viviid emissions reductions universal private Ltd.		
5.	Darne	Minal			
6.	Panigatti	Praveen	Local Stakeholders		
7.	R.	Gurunath			
8.	S.	Prashant			

Sampling approach

Not Applicable.

Clarification request (CLs), corrective action request (CARs) and forward action request (FARs) raised

Areas of Project Verification findings	No. of CL	No. of CAR	No. of FAR
Green House Gas (GHG)			
Identification and Eligibility of project type	-	-	-
General description of project activity	-	-	-
Application and selection of methodologies and standardized baselines	-	-	-
- Application of methodologies and standardized baselines	-	-	-
- Deviation from methodology and/or methodological tool	-	-	-
- Clarification on applicability of methodology, tool and/or standardized baseline	03	-	-
- Project boundary, sources and GHGs	-	-	-
- Baseline scenario	-	-	-

- Estimation of emission reductions or net anthropogenic removals	01	01	-
- Monitoring Report	01	02	-
Start date, crediting period and duration	-	01	-
Environmental impacts	-	-	-
Project Owner- Identification and communication	-	-	-
Others (please specify)	-	-	-
Total	05	04	-

Project Verification findings

Identification and eligibility of project type

Means of Project Verification	The project has an installation of a 24 WEGs (1.25) kw (MH) & 0.225 kw (KA) total 15.65 MW wind power capacity and hence it qualifies as a large-scale project. This is confirmed based on the commissioning certificates and technical specifications. Since the project is a large-scale project, it has applied approved CDM large scale methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0. The Project owner has used valid MR form available at the UCR website for the preparation of MR for the current project activity. The project has prepared MR in line with UCR guidance and requirements.
Findings	No findings raised.
Conclusion	The UCR-approved format is used for description and the project meets the requirement of the UCR verification standard and UCR project standard. UCR project communication agreement was submitted to the verifier and the same has been verified. Methodology referenced and applied appropriately describing the project type. The eligibility of the project aggregator is verified using the UCR communication agreement, project correctly applies the verification standard, UCR project standard, and UCR regulations. The project activity is overall meeting the requirements of the UCR Verification standard and UCR project standard.

General description of project activity

Means of Project Verification	The project activity involves the operation of a 24 WEGs (1.25) kw (MH) & 0.225 kw (KA) total 15.65 MW large-scale wind power project and its commissioning date and power evacuation at the substation were verified through the commissioning certificate of the project. The power purchase agreement confirms the companies/entities involved in the agreement for purchase of electricity from the 15.65 MW (Maharashtra and Karnataka State in India) project.					
	Assessment team conducted documentation review of the PCN against the UCR program verification standard version 2.0 and UCR CoU Standard (project eligibility criteria) version 7.0 and the UCR-PCN-FORM Version 1.0.					
	By checking the supporting documents, it is confirmed that the project is a greenfield wind power project, the project is located in Maharashtra and Karnataka State in India. The approximate geo-coordinates of the project locations are mentioned below.					
	<u>Details of Latitude &Longitude for the project site: -</u>					
	Customer Name	Capacity	Site	Capacity	Geo Coordinates	
				HTSC No.		Total Mw
	Inno Automation India Pvt Ltd	1.25	Sakri	K295		15.65
	Inno Automation India Pvt Ltd	1.25	Sangli	G06		
	Intech Automation Pvt Ltd	1.25	Sakri	K103		
	Intech Automation Pvt Ltd	1.25	Sakri	K104		
	Intech Power Kovai Pvt Ltd	1.25	Sakri	K294		
	Intech Systems Chennai Pvt Ltd	1.25	Sakri	K132		
	Intech Systems Chennai Pvt Ltd	1.25	Sakri	J095		
	Intech Systems Chennai Pvt Ltd	1.25	Sakri	J096		
	Intech Systems Chennai Pvt Ltd	1.25	Sakri	J097		
	Intech Systems Chennai Pvt Ltd	1.25	Sakri	J098		
	Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 01		
Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 02			
Intech Systems Chennai Pvt Ltd	0.675	Gadag	IGT 03, 04 & 08			
Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 05			
Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 07			
Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 10			
Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 11			

	Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 12	15°20'04.6"N , 75°36'31.1"E
	Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 31	15°20'15.4"N , 75°36'23.5"E
	Intech Systems Chennai Pvt Ltd	0.45	Gadag	IGT 32 & 34	15°20'12.4"N , 75°36'17.5"E
	Intech Systems Chennai Pvt Ltd	0.225	Gadag	IGT 33	15°19'46.2"N , 75°36'19.0"E
Assessment team performed an offsite inspection of project and confirmed that the location described in the PCN are accurate. The Project is a wind power project, to utilize wind energy to generate zero carbon emission electricity which is mainly dominated by fossil fuel power output. The project includes integrated power transmission mechanism, high performance rotor blades, dual speed asynchronous generator, microprocessor based fully automatic control system with user friendly operation and central monitoring system. Quality, Safety and Health plan for construction, installation, commissioning and Operation & Maintenance. Microprocessor controlled high efficiency soft start. Active Yaw gear drives incorporating hydraulic yaw brakes.					
Findings	No findings raised.				
Conclusion	The description of the project activity is verified to be true based on the review of PCN, MR, Commissioning Certificate and power purchase agreement.				

Application and selection of methodologies and standardized baselines

(.a.i) Application of methodology and standardized baselines

Means of Project Verification	The project has taken the reference of CDM methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0. CDM website is referred to check the latest version of the methodology. For the applicability mentioned in the PCN and MR, technical Specification, and commissioning certificate.
Findings	No findings raised.
Conclusion	The methodology applied is appropriately meeting the requirements of UCR and its standardized baseline. The methodology version is correct and valid. The referenced methodology is applicable to project activity.

(.a.ii) Clarification on applicability of methodology, tool and/or standardized baseline

Means of Project Verification	The documents reviewed are CDM methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0, UCR Program standard, and UCR Verification Standard.
Findings	CL 01, CL 02 and CL 03 were raised and closed successfully. More information presented in the appendix below.
Conclusion	The verification team confirms that all the applicability criteria set by the applied CDM methodology and its eligible tools are met. The relevant information against those criteria is also included in the PCN version 1.2 and MR version 1.1. The selected CDM methodology for the project activity is applicable.

(.a.iii) Project boundary, sources and GHGs

Means of Project Verification	Project owner has considered project boundary as per applicable methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0, "the spatial extent of this project activity includes the project site and all the power plants connected physically to the electricity system (grid) that the power project is connected to." Review of PCN and MR confirms that project sites and Indian electricity grid system is considered as a project boundary which is appropriate.
Findings	No findings raised
Conclusion	The project boundary is correctly defined in the PCN and MR. GHG sources are correctly identified and reported. The project meets the requirements of UCR project standard, Verification standard and methodology requirements for a boundary, GHG sources.

(.a.iv) Baseline scenario

Means of Project Verification	As per the applied ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources - Version 22.0 the baseline scenario is as following: The baseline scenario is that if the project activity is the installation of a Greenfield power plant, the baseline scenario is electricity delivered to the grid by the project activity would have otherwise been generated by the operation of grid-connected power plants and by the addition of new generation sources to the grid. Remote audit conducted and document review showed that in absence of the project activity, the generated electricity would have been supplied by the Indian grid which is dominated by fossil fuel fired plants.
Findings	No findings raised.
Conclusion	The approved baseline methodology has been correctly applied to identify a realistic and credible baseline scenario, and the identified baseline scenario most reasonably represents what would occur in the absence of the proposed UCR project activity. All the assumption and data used by the project participants are listed in the PCN and/or supporting documents. All documentation relevant for establishing the baseline scenario are correctly quoted and interpreted in the PCN. Assumptions and data used in the identification of the baseline scenario are justified appropriately, supported by evidence and can be deemed reasonable.

(.a.v) Estimation of emission reductions or net anthropogenic removal

Means of Project Verification	The project verification team checked whether the equations and parameters used to calculate GHG emission reductions or net anthropogenic GHG removals for PCN and MR are in accordance with applied methodology. Project verification team checked section B.5 and C.5.1 of the PCN & MR respectively to confirm whether all formulae to calculate baseline emissions, project emission and leakage have been applied in line with the underlying methodology.
--------------------------------------	---

	The emission reduction calculation has been carried out as per the CDM methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0 As per the CDM approved ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0 paragraph 57, encompass solely the CO₂ emissions stemming from electricity generation in power plants displaced by the project activity. The methodology operates on the assumption that any electricity generation exceeding baseline levels would have originated from established grid-connected power plants and the integration of new grid-connected power plants. $BE_y = EG_{PJ, y} \times EF_{grid, CM, y}$ Where; BE_y : Baseline emissions in year y (tCO₂/year) EG_{PJ, y} : Quantity of net electricity generation that is produced and fed into the grid as a result of the implementation of the UCR project activity in year y (MWh/year) EF_{grid, CM, y} : Combined margin CO₂ emission factor for grid connected power generation in year y (tCO₂/MWh) A "grid emission factor" refers to a CO₂ emission factor (tCO₂/MWh) which will be associated with each unit of electricity provided by an electricity system. The UCR recommends an emission factor of 0.9 tCO₂/MWh for the 2013-2023 years as a fairly conservative estimate for Indian projects not previously verified under any GHG program. Also, for the vintage 2021, the combined margin emission factor calculated from CEA database in India results into higher emission than the default value. Hence, the same emission factor has been considered to calculate the emission reduction under conservative approach.² Similarly, for the year 2024, a grid emission factor of 0.757 tCO₂/MWh is to be applied. These conservative factors are used to calculate emission reductions. In order to facilitate adoption of authentic baseline emissions data and in keeping with the principle of "conservativeness," all UCR Indian RE projects shall use the new conservative grid emission factor of 0.757 tCO₂/MWh in their emission reduction calculations for the 2024 vintage year. https://medium.com/@UniversalCarbonRegistry/ucr-cou-standard-update-2024-vintage-ucr-indian-grid-emission-factor-announced-ddb790cdc603 Project emissions: Regarding project emissions, ACM0002 version 22.0 specifies that only emissions related to fossil fuel combustion, emissions from the operation of geothermal power plants due to the release of non-condensable gases, and emissions from water reservoirs of hydroelectric plants should be taken into account. Since the project involves a wind power project, emissions from renewable energy plants are negligible PE_y = 0. Since wind power is a GHG emission free source of energy project emission considered as Zero
--	--

² https://a23e347601d72166dcd6-16da518ed3035d35cf0439f1cdf449c9.ssl.cf2.rackcdn.com/Documents/UCRStandardAug2024updatedVer7_020824191534797526.pdf

for the project activity.

Leakage Emissions: Leakage, as outlined in ACM0002 version 22.0, para 5.6, is considered to be zero as there is no transfer of energy-generating equipment in the project activity

Hence ($LE_y = 0$).

Emission reductions: As per approved ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0, emission reduction is estimated as difference between the baseline emission and project emission after factoring into leakage.

Thus, $ER_y = BE_y - PE_y - LE_y$

Where:

ER_y = Emission reductions in year y (t CO₂)

BE_y = Baseline Emissions in year y (t CO₂)

PE_y = Project emissions in year y (t CO₂)

LE_y = Leakage emissions in year y (t CO₂)

Therefore, $ER_y = BE_y$

The earliest commissioning date of the Project is 30/06/2005 when the first installation of the wind turbine was done and the last commissioning date is 13/08/2008.

The start date of the crediting period under UCR is considered from 01/09/2020.

For the ease of the calculation, duration of the crediting period in UCR is started from 01/09/2020 to 31/12/2024.

The estimated emission reductions are 27,026 CoUs/yr (27,026 tCO₂eq/yr)

Year	Net Generation	Baseline Emissions	Project Emissions	Leakage	Emission Reductions	EF
	MWh	(tCO ₂ e)	(tCO ₂ e)	(tCO ₂ e)	(tCO ₂ e)	(tCO ₂ /MWh)
Year 1	31531.62	28378.46	0.00	0.00	28378.46	0.9
Year 2	31531.62	28378.46	0.00	0.00	28378.46	0.9
Year 3	31531.62	28378.46	0.00	0.00	28378.46	0.9
Year 4	31531.62	28378.46	0.00	0.00	28378.46	0.9
Year 5	31531.62	28378.46	0.00	0.00	28378.46	0.9
Year 6	31531.62	28378.46	0.00	0.00	28378.46	0.9
Year 7	31531.62	28378.46	0.00	0.00	28378.46	0.9
Year 8	31531.62	23869.44	0.00	0.00	23869.44	0.9
Year 9	31531.62	23869.44	0.00	0.00	23869.44	0.9
Year 10	31531.62	23869.44	0.00	0.00	23869.44	0.757

	Total Emission reduction	315316	270257	0	0	270257		
	Average Emission Reduction	31532	27026	0	0	27,026		
	The actual emission reduction achieved during the first CoU's period (01/09/2020 to 31/12/2024) as per the Project Activity:							
	Actual Total baseline emission reductions (BEy)= 69,161 CoUs (69,161 tCO2eq)							
	Sr. No.	Year	Capacity	Total EGy ,Net Generation	Emission Factor	Baseline Emissions (BE)	Project Emissions (PE)	Emission Reductions
			MW	kWh	tCO2/ mWh	tCO2e	tCO2e	tCO2e
	1	01-06-2020 to 31-12-2020	15.65	2179934.372	0.9	1961	0	1961
	2	01-01-2021 to 31-12-2021		27185237.02	0.9	24466	0	24466
	3	01-01-2022 to 31-12-2022		16489277.44	0.9	14840	0	14840
	4	01-01-2023 to 31-12-2023		18353956.34	0.9	16518	0	16518
5	01-01-2024 to 31-12-2024	15028566.4		0.757	11376	0	11376	
	Total		79236971.56 79236.97 MWh		69161		69,161	
Findings	CL 04 and CAR 01 were raised and closed successfully. More information presented in the appendix below.							
Conclusion	In summary, the calculation of emission reductions was correctly demonstrated by the PP according to the methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0. It is confirmed by the assessment team that: (a) All assumptions made for estimating GHG are listed in the PCN; (b) All documentation used by the project participants as the basis for assumptions and source of data is correctly quoted and interpreted in the PCN (c) All values used in the PCN including GWPs are considered reasonable in the context of the proposed UCR project activity; (d) The methodologies and, where applicable, the standardized baselines and the other methodological regulatory documents have been applied correctly to calculate baseline, project and leakage GHG emissions, as well as GHG emission reductions; (e) All estimates of the baseline GHG emissions can be replicated using the data and							

	parameter values provided in the PCN;
--	---------------------------------------

(.a.vi) **Monitoring Report**

Means of Project Verification

Parameters determined- Ex-ante

The following parameters are determined ex-ante and verified by the verification team:

The baseline emission factor ($EF_{grid, y}$) of the project is reported to be determined ex-ante and would remain fixed for the crediting period. A "grid emission factor" refers to a CO₂ emission factor (tCO₂/MWh) which will be associated with each unit of electricity provided by an electricity system. The UCR recommends an emission factor of 0.9 tCO₂/MWh for the 2013-2023 years as a fairly conservative estimate for Indian projects not previously verified under any GHG program. Also, for the vintage 2021, the combined margin emission factor calculated from CEA database in India results into higher emission than the default value. Similarly, for the year 2024, a grid emission factor of 0.757 tCO₂/MWh is to be applied. These conservative factors are used to calculate emission reductions.

In order to facilitate adoption of authentic baseline emissions data and in keeping with the principle of "conservativeness," all UCR Indian RE projects shall use the new conservative grid emission factor of 0.757 tCO₂/MWh in their emission reduction calculations for the 2024 vintage year

Hence, the same emission factor has been considered to calculate the emission reduction under conservative approach. The parameters applied in the calculation were validated by the verification team. The verification team confirms that all relevant parameters have been sufficiently considered and the values of the parameters are real, measurable and conservative.

Parameters monitored ex-post

According to the approved methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0, the following parameters will be monitored:

Parameter	Description
$EG_{pj,y}$	Quantity of net electricity generation supplied by the project plant/unit to the grid in year y

The values of the parameters monitored were checked against submitted Joint Meter Readings and invoices and were found correct.

Meter Details:

CALIBRATION DATA							
Sr.no	Meter Type	Meter Sr. No.	Sub-station	Accuracy class	Make	Calibration Details	Calibration Validity
K295	Main Meter	14796470	Valve /220kv	0.2	ELSTER ALPHA A1800	21.10.2023	20.10.2028
	Check meter	14796436	Valve /220kv	0.2	ELSTER ALPHA A1800	21.10.2023	20.10.2028
K294	Main	14796470	Valve	0.2	L&T	31.07.2024	31.06.2029

Project Verification Report

		meter		/220kv				
		Check meter	14796436	Valve /220kv	0.2	ELSTER ALPHA A1800	21.10.2023	20.10.2028
	k104	Main meter	2839067	Jamde /220kv	0.2	ELSTER ALPHA A1800	04.06.2024	03.06.2029
		Check meter	2839066	Jamde /220kv	0.2	ELSTER ALPHA A1800	04.06.2024	03.06.2029
	k103	Main meter	2839067	Jamde /220kv	0.2	ELSTER ALPHA A1800	04.06.2024	03.06.2029
		Check meter	2839066	Jamde/ 220kv	0.2	ELSTER ALPHA A1805	04.06.2024	03.06.2029
	k132	main meter	2814530	Jamde /220kv	0.2	ELSTER ALPHA A1800	04.06.2024	03.06.2029
		Check meter	2814535	Jamde /220kv	0.2	ELSTER ALPHA A1800	04.06.2024	03.06.2029
	J95	Main meter	2839063	Jamde /220kv	0.2	ELSTER ALPHA A1800	04.06.2024	03.06.2029
		Check meter	2839062	Jamde /220kv	0.2	ELSTER ALPHA A1800	04.06.2024	03.06.2029
	J96	Main meter	2839063	Jamde /220kv	0.2	ELSTER ALPHA A1800	04.06.2024	03.06.2029
		check meter	2839062	Jamde /220kv	0.2	ELSTER ALPHA A1800	04.06.2024	03.06.2029
	J97	Main meter	2839063	Jamde /220kv	0.2	ELSTER ALPHA A1800	04.06.2024	03.06.2029
		check meter	2839062	Jamde /220kv	0.2	ELSTER ALPHA A1800	04.06.2024	03.06.2029
	J98	Main meter	2839063	Jamde /220kv	0.2	ELSTER ALPHA A1800	04.06.2024	03.06.2029
		check meter	2839062	Jamde /220kv	0.2	ELSTER ALPHA A1800	04.06.2024	03.06.2029
	G006	MAIN METER	14796421	Jamde /220kv	0.2	ELSTER ALPHA A1800	04.06.2024	03.06.2029
	G-01	MAIN METER	7022930	Gadag 110/33kv	0.2	L & T	31.07.2024	31.06.2029
		CHECK METER	7022969	Gadag 110/33kv	0.2	L & T	31.07.2024	31.06.2029
	G-03, G04, G08	MAIN METER	7022918	Gadag 110/33kv	0.2	L & T	31.07.2024	31.06.2029
		CHECK METER	7022904	Gadag 110/33kv	0.2	L & T	31.07.2024	31.06.2029
	G-05	MAIN METER	7022956	Gadag 110/33kv	0.2	L & T	31.07.2024	31.06.2029
		CHECK	7022946	Gadag	0.2	L & T	31.07.2024	31.06.2029

		METER		110/33kv				
	G-07	MAIN METER	7022960	Gadag 110/33kv	0.2	L & T	31.07.2024	31.06.2029
		CHECK METER	7022938	Gadag 110/33kv	0.2	L & T	31.07.2024	31.06.2029
	G-10	MAIN METER	7022953	Gadag 110/33kv	0.2	L & T	31.07.2024	31.06.2029
		CHECK METER	7022923	Gadag 110/33kv	0.2	L & T	31.07.2024	31.06.2029
	G-11	MAIN METER	22005279	Gadag 110/33kv	0.2	L & T	31.07.2024	31.06.2029
		CHECK METER	7022914	Gadag 110/33kv	0.2	L & T	31.07.2024	31.06.2029
	G-12	MAIN METER	7022964	Gadag 110/33kv	0.2	L & T	31.07.2024	31.06.2029
		CHECK METER	7022941	Gadag 110/33kv	0.2	L & T	31.07.2024	31.06.2029
	G-31	MAIN METER	7022948	Gadag 110/33kv	0.2	L & T	02.08.2024	02.07.2029
		CHECK METER	7022933	Gadag 110/33kv	0.2	L & T	02.08.2024	02.07.2029
	G32, G33, G34	MAIN METER	7022961	Gadag 110/33kv	0.2	L & T	02.08.2024	02.07.2029
		CHECK METER	7022928	Gadag 110/33kv	0.2	L & T	02.08.2024	02.07.2029

There is calibration delay of Maharashtra turbine location no G06 for the monitoring period from 01/09/2020 to 31/12/2024. The error factor has been applied in net export values for the delayed period as meters were not calibrated as per the calibration frequency which is once in five years. As per the Appendix calibration of the VVS Standard v3.0, Para 366(a): error factor of " $\pm 0.2\%$ " should be applicable for both export & import i.e. the measured values. However, net electricity generation is considered as per the registered monitoring plan, the separate export and import values are not available. Hence being conservative and to account for the error for both export & import, a cumulative error of " -0.4% " on net electricity generation has been applied for delay period.³

Calibration of meters was done as per the CEA regulations.

Management system and quality assurance

The monitoring plan presented in the PCN complies with the requirements of the applicable methodology. The verification team has verified all parameters in the monitoring plan against the requirements of the methodology and no deviations have been found.

The management system and quality assurance procedures have been reviewed by the verification team through document review and interviews with the project participant. The project participant would train all the monitoring staffs are trained against with related requirement; the training guidelines and monitoring manual are saved and verified.

The monitoring plan outlines in the PCN includes:

- Monitoring Organization
- Monitoring apparatus and installation
- Calibration
- Data collection

³ https://cdm.unfccc.int/sunsetcms/storage/contents/stored-file-20210921115831128/reg_stan06_v03.0.pdf?

	- Data Management system The submitted calibration certificates were checked and it was confirmed that the calibrations are conducted periodically as specified in the PCN i.e. at least once in 5 years.
Findings	CL 05, CAR 03 and CAR 04 were raised and closed successfully. More information presented in the appendix below.
Conclusion	The verification team is convinced of compliance of the monitoring plan with the requirements of the monitoring methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources - Version 22.0. During the remote audit assessment, the verification team interviewed the PP that the monitoring arrangements described in the monitoring plan are feasible within the project design. The monitoring parameter reported in MR adequately represents the parameters relevant to emission reduction calculation. The calibration report ensures the accuracy of the data reported. The number of CoUs generation is calculated based on this accurately reported data. The calculation was done using an excel sheet where all the parameters were reported. The grid emission factor for electricity is considered as per UCR recommendation for Indian project. In the monitoring report, emission reduction calculations are correctly calculated and reported. The monitoring report meets the requirements of UCR project verification requirements.

Start date, crediting period and duration

Means of Project Verification	The start date and crediting period of project activity was checked based on the commissioning certificate, PCN, MR and other documents provided.
Findings	CAR 02 was raised and closed successfully. More information presented in the appendix below.
Conclusion	The project has chosen crediting period start date in UCR as 01/09/2020. The crediting period is chosen as 01/09/2020 to 31/12/2024 and the crediting period for the current monitoring period is 01/09/2020 to 31/12/2024.

Positive Environmental impacts

Means of Project Verification	PP has not claimed any separate positive environmental impact. The project being renewable energy project will reduce fossil fuel use through replacement of the same.
Findings	No findings raised
Conclusion	The project is a renewable energy project and reduces the environmental burden by reducing the dependence on fossil fuel-based power plants.

Project Owner- Identification and communication

Means of Project Verification	PCN, communication agreement, MR, commissioning certificate, power purchase agreement.
Findings	No findings raised.
Conclusion	The project owner was identified through a communication agreement signed between project owner and project aggregator. Commissioning certificates and Power Purchase Agreement were

	also verified and they clearly establish the project ownership. The identification and communication correctly meet the requirement of project verification and UCR project standard. Project owner: Inno Automation, Intech Automation, Intech Power Kovai, Intech Power Chennai Pvt Ltd.
--	--

Positive Social Impact

Means of Project Verification	Project has provided temporary employment to local people during its installation and commissioning. Also post commissioning some of people have employed permanently and local people were engaged leading to social financial benefit to surrounding. Overall social impact of project implementation is positive on the surrounding area
Findings	No findings raised.
Conclusion	Project has overall positive social impact

Sustainable development aspects (if any)

Means of Project Verification	PP has claimed SDG Goals 7, 8 & 13. SDG 7 is affordable and clean energy and it is verified during remote audit as the project is solar power plant. SDG 8 is decent work & economic growth and is verified by the supporting documents provided. SDG 13 is climate action. These claims were checked on the basis of supporting documents, JMR & invoice, employment of the local people on the project site and emission reduction calculations respectively.
Findings	No findings raised.
Conclusion	The project has the capability to address SDG 7, 8 and 13.

Internal quality control

The verifier confirms that,

- Due professional care has been taken while reviewing the submitted document.
- There is no conflict of interest as the verifier has no other engagement with either the aggregator or project owner directly or indirectly.
- Verification team consists of experienced personnel.

Project Verification opinion

Assessment team conducted documentation review the PCN against the UCR program verification standard version 2.0 and UCR project eligibility criteria version 7.0 and the UCR-PCN-FORM Version 1.0.

It is confirmed that the project activity is a 15.65 MW of large-scale wind power project located across villages of Sakri in Maharashtra & villages in Bhelahadi Karnataka state in India.

The geo co-ordinates of the project activity have been mentioned in sections above. Assessment team performed a remote audit and confirmed that the location described in the PCN is accurate. The verification was performed on the basis of UCR requirements, and host country criteria, as well as criteria given to provide for consistent project operations, monitoring and reporting.

The verification consisted of the following three phases: i) desk review of the PCN, MR and additional background documents; ii) follow-up interviews with project stakeholders; iii) resolution of outstanding issues and the issuance of the final verification report and opinion.

The project correctly applies the approved baseline and monitoring methodology ACM0002-Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0.

The monitoring plan provides for the monitoring of the project's emission reductions. The monitoring arrangements described in the monitoring plan are feasible within the project design, and the project participants are able to implement the monitoring plan. Given that the project is implemented and maintained as designed, the project has achieved the emission reductions of 69,161 tCO₂eq during the monitoring period i.e. from 01/09/2020 to 31/12/2024.

The review of the project design documentation and the subsequent follow-up interviews have provided assessment team with sufficient evidence to determine the fulfilment of stated criteria. In our opinion, the project meets all applicable UCR requirements. Assessment team thus requests the registration of the proposed UCR project activity.

Appendix 1. Abbreviations

Abbreviations	Full texts
ACM	Approved Consolidated Methodology
UCR	Universal Carbon Registry
PCN	Project Concept Note
MR	Monitoring Report
t	Tonnes
NGO	Non-Governmental Organization
ISO	International Organization for Standardization
CAR	Corrective Action Request
CL	Clarification Request
GHG	Greenhouse Gas
MWh	Megawatt Hours
CO ₂	Carbon Dioxide
CH ₄	Methane
N ₂ O	Nitrous Oxide

Appendix 2. Competence of team members and technical reviewers

❖ **Ms. Swati Mahajan** is graduate in Environmental Engineering from Shivaji University, India and previously worked as an Environment Engineer at Eco Designs India Private Ltd., Pune. She is adept in designing of landfill sites for solid waste management. She also has hands on experience in cost benefit analysis and preparation of DPRs for SWM projects. She also has done a certified course in carbon capture and storage from Edinburg University. Currently working as GHG assessor for projects under various GHG mechanisms like GCC, ICR, UCR and VERRA.

❖ **Ms. Ritu Singh** has done Masters in Environmental Science from Central University of South Bihar, Gaya and bachelor of Science in Zoology from Magadh Mahila College, Patna University, India. She has done Masters' research focused on solid waste management during and post covid-19 pandemic and conducted a survey in Medical Colleges of Bihar to study the trends of waste management. She has more than 2 year working experience in True Quality Certifications Pvt. Ltd. (An outsource entity for LGAI Technological Center, S.A. (Spain) "Applus+ Certification") and has been involved in supporting Audit teams for Validation and Verifications of Project Activities (Renewable and non-Renewable projects) under CDM/VCS/GS4GG/GCC programs. Currently, Ritu is engaged as an internal resource with Enviance Services Private Limited, where she is accredited as a Lead Auditor, Validator, Verifier, and Technical Expert for Sectoral Scope/Technical Area 1.2 by Enviance.

❖ **Mr. Pankaj Kumar** is a seasoned Environment and Climate Change professional with over 19 years of experience in Climate Change Mitigation & Adaptation, Environmental Due Diligence, Disaster Risk Reduction, Climate Finance, and capacity building. As the Managing Director of Enviance Services Pvt. Ltd., Pankaj Kumar leads a validation and verification body for GHG projects and also providing consultancy services in various areas including Climate Adaptation, Mitigation, Sustainability, and more. Previously, Pankaj Kumar served as a Climate Adaptation Expert with Deloitte Touche Tohmatsu India LLP, contributing to the World Bank project on Asset Management, Institutional Effectiveness, and Road Safety in Bihar. Mr. Pankaj also led the Bihar team for the South Asia Climate Proofing and Growth Development (CPGD) – Climate Change Innovation Programme (CCIP), supported by DFID, which aimed to integrate climate change resilience into planning and budgeting across South Asia. With a strong background in environmental projects, Pankaj Kumar has worked with IL&FS Infrastructure Development Corporation and BUIDCO (Bihar Urban Infrastructure Development Corporation) as an Environmental Specialist for WB & ADB funded projects. Additionally, Pankaj has extensive experience in GHG project validation and verification, having led over 300 projects globally while with UNFCCC accredited DoEs and as an external expert for Gold Standard and Global Carbon Council. Mr. Pankaj is an accredited Lead Auditor, Validator, Verifier, and Technical Expert for multiple sectoral scopes by UNFCCC DoE and is on the roster of WASH experts of UNICEF. Mr. Pankaj's expertise spans across various standards including CDM, Verified Carbon Standard, Gold Standard, Global Carbon Council, Natural Forest Standard, Riverse and Social Carbon Standard.

Appendix 3. Document reviewed or referenced

No.	Author	Title	References to the document	Provider
1	NA	Communication agreement		Project Owner
2	NA	Project Concept Note		Aggregator
3	NA	Monitoring report		Aggregator
4	NA	Emission reduction sheet		Aggregator
5	NA	Declaration on avoidance of doublecounting		Aggregator
6	NA	Commissioning Certificates for the wind power plants		Aggregator
7	NA	Power purchase agreement		Aggregator
8	NA	Joint Meter Readings/invoices for the complete monitoring period		Aggregator
9	NA	Calibration certificates for energy meters		Aggregator
10	NA	Equipment purchase order		Aggregator
11	NA	Grid Emission factor recommended for Indian projects by UCR	Upto year 2023 - https://a23e347601d72166dcd6-16da518ed3035d35cf0439f1cdf449c9.ssl.cf2.rackcdn.com/Documents/UCRStandardAug2024updatedVer7_020824191534797526.pdf Year 2024 - https://medium.com/@UniversalCarbonRegistry/ucr-cou-standard-update-2024-vintage-ucr-indian-grid-emission-factor-announced-ddb790cdc603	General project eligibility criteria and guidance UCR standard version 7.0
12	UCR	UCR Program manual version 6.2 UCR COU standard version 7 UCR Verification standard version 2 UCR terms and conditions version 11.0, May 2025	https://www.ucarbonregistry.io/Document?projectId=1	Universal Carbon Registry
13	CDM	CDM approved methodology- ACM0002- Consolidated baseline methodology for grid-connected electricity generation from renewable sources -Version 22.0.	https://cdm.unfccc.int/met hodologies/DB/XB1TX7T AZ6SLWM9B7BC67THH VD16JV	UNFCCC

Clarification request, corrective action request and forward action request

Table 1. CLs from this Project Verification

Classification	☐ CAR ☒ CL/CR ☐ FAR	Number:	01
Raised by:	Ms. Swati Mahajan	Document Reference	MR
Finding Description		Date:	13/08/2025
- PP shall submit the single line diagram of the project activity. - PP shall submit the PPA of Karnataka region. - PP shall submit supporting document of technical specifications of wind turbine of both 1.25 MW and 0.225 MW as mentioned in PCN.			
Client/Responsible Party/Project Proponent Response		Date:	16/08/2025
- PP has submitted the single line diagram - PP has submitted the PPA of Karnataka region. - PP has submitted the technical specifications of wind turbine 1.25 MW (MH) & "KA turbine's capacity and model are already certified in the PPA, commissioning, and JMR; hence, separate specifications were not maintained."			
Validation/Verification Team Assessment		Date:	27/08/2025
- PP has submitted the single line diagram of the project activity of both Maharashtra and Karnataka location and the same was assessed. - PP has submitted the PPA of Karnataka region. All the information mentioned in MR is found to be consistent with the PPA. - PP has submitted supporting document of technical specifications of wind turbines and all the specifications mentioned in MR are found to be consistent. Hence, CL 01 is closed.			

Classification	☐ CAR ☒ CL/CR ☐ FAR	Number:	02
Raised by:	Ms. Swati Mahajan	Document Reference	MR
Finding Description		Date:	13/08/2025
PP shall submit the names of the local stakeholders.			
Client/Responsible Party/Project Proponent Response		Date:	16/08/2025
PP has submitted the names of the local stakeholders			
Validation/Verification Team Assessment		Date:	27/08/2025
PP has submitted the list of the names of the local stakeholders. Hence, CL 02 is closed.			

Classification	☐ CAR ☒ CL/CR ☐ FAR	Number:	03
Raised by:	Ms. Swati Mahajan	Document Reference	MR

Project Verification Report

Finding Description	Date:	13/08/2025
PP shall submit the meter photographs of Karnataka region along with meter calibration report of all 14 locations.		
Client/Responsible Party/Project Proponent Response	Date:	16/08/2025
1. PP has submitted the meter photographs of Karnataka region along with meter calibration report of all 14 locations.		
Validation/Verification Team Assessment	Date:	27/08/2025
PP has submitted the meter photographs of Karnataka region. The meter serial numbers mentioned in MR are consistent with the meter photographs. PP has submitted the meter calibration report of Karnataka region. All the information mentioned in MR is found to be consistent. Hence, CL 03 is closed.		

Classification	☐ CAR ☒ CL/CR ☐ FAR	Number:	04
Raised by:	Ms. Swati Mahajan	Document Reference	MR
Finding Description		Date:	13/08/2025
1. PP shall submit supporting documents of few JMR readings. 2. PP shall submit commissioning certificate of locations K 103 and K 104.			
Client/Responsible Party/Project Proponent Response		Date:	16/08/2025
1. PP has submitted supporting documents of few JMR readings. 2. PP has submitted the commissioning certificate of locations K 103 & k104			
Validation/Verification Team Assessment		Date:	27/08/2025
1. PP shall submit supporting documents of few JMR readings. PP requested to read the comment written in front of the highlighted box in excel sheet. 2. PP has submitted commissioning certificates of locations K 103 and K 104. Dates mentioned in MR is found to be consistent with the submitted commissioning certificates. Hence, CL 04 is open.			
Client/Responsible Party/Project Proponent Response		Date:	29/08/2025
1. PP has submitted the supporting documents of few JMR readings.			
Validation/Verification Team Assessment		Date:	09/09/2025
1. PP has submitted the supporting documents of all JMR readings. 2. PP has submitted commissioning certificates of locations K 103 and K 104. Dates mentioned in MR is found to be consistent with the submitted commissioning certificates. Hence, CL 04 is closed.			

Classification	☐ CAR ☒ CL/CR ☐ FAR	Number:	05
Raised by:	Ms. Swati Mahajan	Document Reference	MR
Finding Description		Date:	13/08/2025
In monitoring report, PP shall mention details of all the locations of Maharashtra and Karnataka clearly along with number of turbines and capacity.			
Client/Responsible Party/Project Proponent Response		Date:	16/08/2025
1. PP has mentioned the details of all the locations of Maharashtra and Karnataka clearly along with			

number of turbines and capacity.		
Validation/Verification Team Assessment	Date:	27/08/2025
PP has mentioned details of all the locations of Maharashtra and Karnataka clearly along with number of turbines and capacity in MR. During assessment it was verified in MR version 1.1. Hence, CL 05 is closed.		

Table 2. CARs from this Project Verification

Classification	☒ CAR ☐ CL/CR ☐ FAR	Number:	01
Raised by:	Ms. Swati Mahajan	Document reference	MR
Finding Description		Date:	13/08/2025
1. Few JMR readings are inconsistent with the submitted supporting documents. Correction sought. 2. PP shall revise the energy generation and emission reduction value in MR as per the revised excel sheet.			
Client/Responsible Party/Project Proponent Response		Date:	16/08/2025
1. PP has corrected the Few JMR readings which was inconsistent with the submitted supporting documents. 2. PP has revised the energy generation and emission reduction value in MR as per the revised excel sheet.			
Validation/Verification Team Assessment		Date:	27/08/2025
1. Few JMR readings are inconsistent with the submitted supporting documents. Correction sought. PP requested to read the comment written in front of the highlighted box in excel sheet. 2. PP shall revise the energy generation and emission reduction value in MR as per the revised excel sheet. Hence, CAR 01 is open			
Client/Responsible Party/Project Proponent Response		Date:	30/08/2025
1. PP has corrected the Few JMR readings which was inconsistent with the submitted supporting documents. 2. PP has revised the energy generation and emission reduction value in MR as per the revised excel sheet.			
Validation/Verification Team Assessment		Date:	09/09/2025
1. Few JMR readings are inconsistent with the submitted supporting documents. Correction sought. 2. PP shall revise the energy generation and emission reduction value in MR as per the revised excel sheet. Hence, CAR 01 is open			
Client/Responsible Party/Project Proponent Response		Date:	08/01/2026
1. PP has submitted the JMR readings which were inconsistent with the submitted supporting documents. 2. PP has revised the energy generation and emission reduction value in MR as per the revised			

Project Verification Report

excel sheet.		
Validation/Verification Team Assessment	Date:	08/01/2026
1. PP has made corrections in the JMR readings and on assessment it was verified that the readings are now consistent with the submitted documents. 2. PP has revised the energy generation and emission reduction value in MR version 1.1 as per the revised excel sheet and on verification all the values were found to be consistent. Hence, CAR 01 is closed		

Classification	☒ CAR ☐ CL/CR ☐ FAR	Number:	02
Raised by:	Ms. Swati Mahajan	Document Reference	PCN
Finding Description		Date:	13/08/2025
1. Commissioning dates of all the locations is inconsistent with the submitted commissioning certificates. Correction sought. 2. First issuance period date is inconsistent throughout the MR and also with the excel ER sheet. Correction required in both MR and excel sheet.			
Client/Responsible Party/Project Proponent Response		Date:	16/08/2025
1. PP has corrected the Commissioning dates of all the locations Which was inconsistent with the submitted commissioning certificates. 2. PP has corrected the First issuance period date which was inconsistent throughout the MR and also with the excel ER sheet. Correction has done in both MR and excel sheet.			
Validation/Verification Team Assessment		Date:	27/08/2025
1. Few commissioning dates are still inconsistent. 2. PP has corrected the first issuance period in MR and now it is consistent with the ER sheet. Hence, CAR 02 is open.			
Client/Responsible Party/Project Proponent Response		Date:	30/08/2025
1. PP has corrected the commissioning dates Which was inconsistent			
Validation/Verification Team Assessment		Date:	09/09/2025
1. All the commissioning dates are now consistent with the submitted commissioning certificates. The same has been verified in MR version 1.1. 2. PP has corrected the first issuance period in MR and now it is consistent with the ER sheet. Hence, CAR 02 is closed.			

Classification	☒ CAR ☐ CL/CR ☐ FAR	Number:	03
Raised by:	Ms. Swati Mahajan	Document Reference	PCN
Finding Description		Date:	13/08/2025
Under section B.8. of PCN, EG _{pj,y} parameter is inconsistent. Corrective action sought.			
Client/Responsible Party/Project Proponent Response		Date:	16/08/2025
PP has corrected section B.8. of PCN. EG _{ni,v} parameter.			

Project Verification Report

Validation/Verification Team Assessment		Date:	27/08/2025
PP has made correction in EG _{proj} parameter in section B.8 of PCN. During assessment it was verified in PCN version 1.1. Hence, CAR 03 is closed.			
Classification	☒ CAR ☐ CL/CR ☐ FAR	Number:	04
Raised by:	Ms. Swati Mahajan	Document Reference	MR
Finding Description		Date:	13/08/2025
In MR, PP shall mention in detail "Why is a 115% multiplier on installed capacity considered for estimating net energy generation in Karnataka, while no such adjustment is applied in Maharashtra?"			
Client/Responsible Party/Project Proponent Response		Date:	16/08/2025
PP has clarified that as per Karnataka's regulatory framework, 115% of the installed capacity is considered for estimating net energy generation. This adjustment factor is stipulated in the prescribed 'B Form' submission requirements, hence it has been applied in our Karnataka calculations. In Maharashtra, there is no such provision or multiplier requirement from MSEDCL; therefore, the installed capacity alone has been considered for calculation without applying the 115% factor."			
Validation/Verification Team Assessment		Date:	27/08/2025
As mentioned above, PP shall add the reason in MR. Hence, CAR 04 is open.			
Client/Responsible Party/Project Proponent Response		Date:	30/08/2025
PP has mentioned this reason below calculation table.			
Validation/Verification Team Assessment		Date:	09/09/2025
The clarification provided by the Project Proponent regarding the application of a 115% multiplier on installed capacity in Karnataka is duly mentioned in MR version 1.1. As stated, this adjustment aligns with the stipulations outlined in the state's regulatory framework and the prescribed 'B Form' submission requirements. The absence of a similar provision in Maharashtra, as per MSEDCL's guidelines, justifies the differential treatment in methodology. From an audit perspective, the approach appears consistent with state-specific regulatory expectations. Hence, CAR 04 is closed.			

Table 3. FARs from this Project Verification

FAR ID	xx	Section no.		Date: DD/MM/YYYY
Description of FAR				
Project Owner's response				Date: DD/MM/YYYY
Documentation provided by Project Owner				
UCR Project Verifier assessment-				Date: DD/MM/YYYY